

# Comparative Risk Analysis of NATM and TBM for Mixed-face Large-Diameter Urban Tunneling

Young-Geun Kim<sup>1</sup>, Joon-Shik Moon<sup>2\*</sup>, Jai-Beom Shim<sup>3</sup>, Seung-Bok Lee<sup>4</sup>, Chang-Rim Choi<sup>5</sup>, Youn-Chul Chun<sup>6</sup>

## 도심지 대단면 복합지반 NATM 과 TBM 터널공법의 비교위험도 분석

김영근, 문준식, 심재범, 이승복, 최창림, 천윤철

**Abstract** The risk assessment is essential for tunnel design in order to minimize risks associated with uncertainty about geological conditions and tunneling method. This paper provides a comparative risk analysis of a large single bore TBM driven tunnel against sequentially excavated NATM tunnel for a mixed-face large-diameter urban tunnel project near or under a river. The focus of this assessment is on the risks associated with the tunnel excavation methods, in particular whether a TBM or NATM presents more or less risk to achieve the planned excavation duration and bring the project within the estimated bid price. First, the impacts and risks to tunnel construction under each method were discussed, and the risks were scored and ranked in the order of perceived severity and likelihood. Finally, the assessment from a risk based perspective was conducted to decide which alternate tunneling method is more likely to deliver the project with the least time and cost. It is very important to note that this study is only applied to this tunnel project with specific geological conditions and other contract requirements.

**Keywords:** Comparative risk analysis, Mixed-face, Large-diameter urban tunnel, NATM vs Shield TBM

**요 지** 터널 공사 중 많은 문제를 야기시킬 수 있는 불확실한 지반상태 및 터널 공법에 따른 여러 리스크를 최소화 할 수 있도록 전반적인 위험도 평가를 터널 설계 시 반드시 수행하여야 한다. 본 연구에서는 도심지 및 하저터널 구간의 터널공법으로 NATM 또는 실드 TBM 적용시 공법별 발생할 수 있는 리스크에 대하여 분석하였다. 우선 연구대상 지역의 주요 리스크 항목을 선정 후 공법적용시 발생 가능한 리스크와 그 영향을 검토하고, 각각의 리스크 발생가능성과 터널공사에 미치는 위험도에 따라 정량적으로 등급화 하였다. 이러한 리스크 분석을 통하여 주요 위험도 영향을 고려한 공사비 및 공기 분석을 수행하고 터널공법별 비교위험도를 평가하였다. 본 연구결과를 바탕으로 복합지반으로 구성된 도심지 대단면 터널에 대해 리스크 발생을 최소화 할 수 있는 안전하고 경제적인 터널공법을 선정하였다. 단, 본 연구는 국한된 지층 및 특별조건에서의 비교위험도를 평가한 결과임을 밝혀둔다.

**주요어:** 비교위험도, 복합지반, 도심지 대단면 터널, NATM vs 실드 TBM

### 1. Introduction

Underground construction involves inherent risks of

geology and linear construction methods that have led to an unwanted reputation for late and over-priced projects around the world. Underground construction has also proven to be exceptionally risky for the insurance companies that underwrite projects for the construction industry. What contribute to increased risk on tunneling projects are limited pre-bid geotechnical investigations, unrealistic cost and schedule expectations, and inappropriate tunneling methodology. For this project the following are the most serious effects of risks associated with delivery of the tunnel:

<sup>1</sup>Member, General Manager, Ph. D., Underground Engineering, Samsung C&T Corp.

<sup>2</sup>Member, Manager, Ph. D., Underground Engineering, Samsung C&T Corp.

<sup>3</sup>Member, Advisor, Samsung C&T Corp.

<sup>4</sup>Member, General Manager, Underground Engineering, Samsung C&T Corp.

<sup>5</sup>Member, Director, Geotechnical Division, Sambo Engineering Co. Ltd.

<sup>6</sup>Member, Executive Vice President, Civil Engineering Business Division, Samsung C&T Corp.

\*교신저자: Joon-Shik Moon (E-mail: joonshik.moon@samsung.com)

- Failure to keep within the bid price
- Failure to achieve the required completion date
- Failure to meet required quality and operational requirements, and
- Experience of an unacceptable or potentially catastrophic event within, adjacent to or above the tunnel.

The assessment in this paper will focus on finding risks associated with the tunneling methods, especially TBM tunneling method and NATM, and determining the tunneling method presenting less risk to complete the project within the estimated bid price and the planned excavation duration. The success of tunnel project is mainly dependent upon achieving planned advance rates during excavation. The ability to recover the partially excavated tunnel in the event of a catastrophic face collapse or flooding of the tunnel should be considered in the risk assessment.

## 2. Project Overview

### 2.1 General

The project requires 4.86km of subsurface excavation providing a 4 lane urban expressway. The subsurface excavation has approximately 4.08km in tunnel with another 0.63km of box structure and 0.15km of U-type section. The tunnel is located as deep as 50m below the ground surface and partially excavated under a river. A number of different alignments and profiles were considered, and the following items were considered in selection of the tunnel alignment:

- Tunnel design, including length, depth, dimensions, shape, and proximity of one tunnel bore to the other
- Historical excavation experience in the area
- Ground conditions, in particular known and potential faults zones including intersecting faults
- Available site access and logistics
- Surface impacts, structures along the alignment,

portal locations, and

- Proximity to the river and possibility of flooding.

The estimated cost of the project is 375.7 Billion Korean Won (\$330 million) with anticipated construction duration of 2,100 days.

### 2.2 Geology

The regional geology consists of Pre-Cambrian banded gneiss with well developed foliation, heavily faulted with mica gneiss and dykes in some parts, overlain with thick alluvial deposits consisting of mainly sands and gravels (Samsung C&T, 2010a). There are two predominant sets of lineaments NNE-SSW to NNW-SSE. The tunnel alignment is close to the lineament that follows the river (NW-SE). The tunnel portals are located in the old alluvial flood plains.

The river itself is a large geologic structure and contains several faults and shear zones. Rock strengths encountered in construction of these other projects were as high as 200MPa. However, mixed faces of high strength rock and completely weathered rock with dyke intrusions were also encountered.

Some detail geologic information is provided from tunnel projects in the project area. Alluvial deposits (sands, gravels and cobbles) were encountered at a depth of 30m. The top of bedrock fluctuated between 10m and 30m from the surface and mixed faces of gravel - weathered rock - bedrock were encountered. Generally rock strengths varied between 87MPa and 187MPa, with quartz content in the range of 35% - 40% and up to 60%.

The tunnels will be constructed mainly in hard gneiss through multiple faults (13 identified and 3 suspected) and there will be an inevitable degree of uncertainty regarding the conditions that will be encountered including, in particular, the hydrogeological conditions. The geological information indicates that the ground conditions are likely to be highly variable and that water inflows are likely to be encountered from discontinuities in the rock, including joints, faults and

dykes at and around tunnel depth. In addition to anticipated water seepage through the joints, when tunneling adjacent to and beneath the river, there is an increased likelihood of significant ground water inflows from wider conductive joints and fault zones.

The geological profile indicates a number of areas where the ground conditions are likely to be very poor and problematic for tunneling. The conditions indicated include:

- Mixed face conditions of rock and soil materials
- Highly variable rock strengths
- Fractured rock in or near known or suspected and/or possible fault zones
- The presence of fractured or highly fractured rock in areas other than fault zones
- Localized weathering in the known, suspected and/or possible fault zones and dykes
- Areas of closely spaced joints
- Highly altered and/or gouge material present in faults and dykes
- Stiff blocks embedded in soft matrix
- Adversely oriented discontinuities and or low angle shear zones
- Abrasive mineralogy

Five rock classifications have been identified, varying in rock mass properties. The average permeability ranges from  $4.4 \times 10^{-4}$  cm/sec in the fault zones to  $6.2 \times 10^{-7}$  cm/sec in Type I. Young's Modulus ranges from 50MPa to 23,000MPa and unconfined compressive strengths (UCS) range from 240MPa in rock Type I to 55MPa in rock Type V. Approximately 70% of the tunnel alignment is expected to be in Type III and IV ground. Rock strength difference could vary up to 30 times within the same cross section face area.

However, approximately 15% of the tunnel alignment appears to cross faults up to 25m to 32m wide with mostly unfavorable orientations (parallel to the tunnel alignment or against the dip), multiple intersecting faults, dykes and shear zones of jointed rock, crushed

rock in a matrix of sand and gravel and or weathered rock. Graphite is present in the fault zones which would be clay like under the influence of water.

There is a wide scatter in the rock mass rating (RMR) from a low of 20 to a high of 80, which would indicate less predictability and more potential for deformation. The brecciated or gouge material in the fault zones appears to be severely fractured to crushed almost gravel-like with zero shear strength. This could correspond to the very high permeabilities in these zones.

### 3. Common Risks Associated with Tunneling Methods

#### 3.1 NATM Tunneling

There are a number of collapses and failures of NATM tunnels in weak rock and soft ground that have resulted in damage to buildings and infrastructure, serious injury and loss of life. The types of collapses that typically occur are :

- Rock falls due to inadequate support
- Crown failures where soil flows into the tunnel under high water pressures
- Local or full face failures where a part or full of the working face runs into the tunnel
- Bench failures where a part or the entire of bench slides transversely or longitudinally into the tunnel
- Washout failures
- Pipe failures

Other types of failure that occur are failures of the lining before and after ring closure, bearing failure of the arch footings, failure due to horizontal movement of the arch footings, and shear failure of the side of the gallery walls. Causes of these collapses are generally attributed to unpredicted geological condition, and technical mistakes on planning, calculation, construction and management.

### 3.2 TBM Tunneling

The constraint of storing precast concrete segments at the construction staging area needs to be considered in the risk assessment. There is a common rule of thumb that “double the average advance rate will be achieved sometime during the project.” For an average advance rate of 7m/day, a peak production rate of 14m/day would be achieved (Samsung C&T, 2010b). Assuming that approximately 1 week’s worth of segments would need to be stored at any one time, this would translate to approximately 40 full rings of segments, which would require a minimum footprint of approximately 800m<sup>2</sup> at the portal, plus an allowance for a gantry crane. The delivery and movement of segments to the portal will also have space limitations.

If the muck is conditioned from an EPB TBM operation, the muck would need to be spread for approximately a week to allow for the muck to dry. The muck pit at the portal would need to be sized to accommodate the multiple loading points and to provide sufficient storage for downtimes when hauling operations are not permitted.

The rock type, rock strength and joint structure are the most fundamental factors governing the boreability and hence TBM advance rate. A “blocky” rock face will inhibit the ability to efficiently cut the rock, and will cause vibrations and accelerated cutter wear if full thrust pressures are maintained. Fall out of hard blocks from a soft matrix caused cutterhead blockages, overloading of conveyor systems, and increased vibrations leading to increased wear on the machines, including the main bearings. High water inflows would also cause fall out of hard blocks and exaggerate

overbreak combined with washout of gouge material.

## 4. Risk Assessment for Tunneling Methods

### 4.1 Analysis Methodology

In this risk assessment, an attempt has been made to assess risks both from a qualitative and quantitative perspective. Risk impacts have two components – cost and schedule. From a qualitative perspective, risks need to be identified and prioritized. For this purpose risk can be assessed as low, medium or high risks based upon a predetermined set of impact values for each category (schedule delay, cost increase and probability of risk occurring) as given in Table 1. The cost and schedule impacts need to take into consideration the possible cumulative risk impact as many risks have the potential for multiple occurrences during repetitive tunneling operation.

A listing and qualitative comparison of risks that have the potential of impacting construction of the project when comparing TBM and NATM approaches are contained in Tables 2, 3 and 4 (Barla and Pelizza, 2000; Barton, 2000; Holen and Anlegg, 1998; Huang, 2008; Tarkoy, 1996; Kim et al, 2002). The probability of encountering each risk factor was assessed using an analysis of historic data on similar projects. The discrete risk events that were considered in the modeling are presented in Table 2. Tables 3 and 4 present the risks that were taken into account when considering the uncertainty in the advance rates for each of the methods. Most events described in Tables 2, 3 and 4 can be characterized by impacting the

**Table 1.** Risk Impact Rating-Impact Matrix

Impact Rating	Low		Medium	High	
	1	2	3	4	5
Schedule Delay	1 day	1 week	1 month	6 months	1 year
Cost Increase (Korean Won)	0.15 billion	1 billion	25 billions	37 billions	50 billions
Probability of Risk Occurring	< 5%	5-25%	25-75%	75-95%	>95%

**Table 2.** Risk Registry –Discrete Risk Events and Risks Contributing to Uncertainty

Risk Description	TBM Impact			NATM Impact		
	Prob.	Cost	Sched	Prob.	Cost	Sched
The following are considered discrete risk events that would have an impact over and above general uncertainty in advance rates.						
A crown failures where soil flows into the tunnel under high water pressures (First Occurrence)				3	3	3
A crown failures where soil flows into the tunnel under high water pressures (Second Occurrence)				2	3	3
A crown failures where soil flows into the tunnel under high water pressures (Third Occurrence)				1	3	3
A bench failure where a part or the entire of bench slides transversely or longitudinally into the tunnel (First Occurrence)				3	3	3
A bench failure where a part or the entire of bench slides transversely or longitudinally into the tunnel (Second Occurrence)				2	3	3
A bench failure where a part or the entire of bench slides transversely or longitudinally into the tunnel (Third Occurrence)				1	3	3
A full face failure in which face, heading and bench flow into the tunnel				1	4	4
Insufficient availability of skilled labor crews to sustain 4 consecutive headings				3	3	4
Delay in delivery procurement, fabrication, and assembly of liner formwork				2		3
Excavation stops due to flooding of the tunnel				1	5	5
Ground freezing required in zones where face supports is unsuccessful.	2	4	4	2	4	4
Excessive settlement of structures or buildings stops excavation while investigations proceed and procedures are modified.	2	3	3	2	3	3
Fire or explosion	1	4	3	1	4	3
Delay in delivery procurement, fabrication, and assembly of TBM	2	2	4			
Substantial exchange rate fluctuations cause increase in imported equipment costs	2	2				

**Table 3.** Risk Registry – Risks Contributing to Uncertainty with Impact Rating

Risk Description	TBM Impact			NATM Impact		
	Prob.	Cost	Sched	Prob.	Cost	Sched
The following risks are considered to contribute to the general uncertainty applied to advance rates in the different ground types						
At the face, fall out of hard blocks from a soft matrix caused cutterhead blockages	2	3	3			
Overloading of conveyor systems	2	3	3			
Increased vibrations leading to increased wear and tear on the machines including the main bearings	2	5	4			
Excessive displacements and fall out of rock wedges	3	3	3			
Excessive wear on the cutterhead and cutters (including Combination of hard, massive and abrasive rock) requiring more than anticipated stoppages for cutter changes	3	4	4			
Potential for mixed face and contaminated ground	5	4	3			
Rock falls due to inadequate support				2	3	3
Inability to control ground water pressures and high water inflows				3	3	3
Difficulty in achieving effective pre-excavation treatment (i.e. grouting)in unstable ground under high water pressure	2	3	3	2	3	3
High water inflows combined with washout of gouge material would exaggerate overbreak which increases required backfill material and sometimes lead to chimney formations	2	3	4	2	3	4
Local face failures where a part of the working face runs in to the tunnel						
Unforeseen ground conditions	3	3	3	3	3	4
Delayed advance rates caused by the need to systematically pre-inject the ground to control or limit ground water inflows	3	3	3	1	3	3

productivity or advance rates achieved in excavation and installation of ground support. The impact of risks can be captured as uncertainty about activities in the construction schedule. It should be noted that the

qualitative comparison of risks is only applied to this tunnel project with specific geological conditions and other contract requirements.

Uncertainty about the construction duration was

**Table 4.** Risk Registry – Other Risks Contributing to Uncertainty without Impact Rating

Risk Description	Uniqueness to Exc. method
The following risks are considered to contribute to the general uncertainty applied to advance rates in the different ground types	
Over-confidence in the method	BOTH
NATM being used in more demanding environments	NATM
NATM being used by those unfamiliar with the technique	NATM
Limitations on pre-excavation grouting patterns increase risk zones of non treated zones	BOTH
Gouge material in the faulted zones contain higher than expected clay content making pre-excavation ground treatment more difficult.	BOTH
Inadequate stand up time allows material to ravel at a faster rate than can be supported resulting in formation of voids or potential chimneys.	NATM
Boring too fast in areas of weakened areas of increased joint frequency leads to instability of the face and crown of the tunnel	TBM
Decelerating progress as excavation distance increases	TBM
Learning curve extended due to rapidly changing ground conditions in first 500m of excavation from either end.	TBM
Excavation blast in competent rock travels into unstable material or fault zones, requires reduction in blast loads and reduced round lengths.	NATM
Large or uncontrolled overbreak results in costly backfilling and reduced productivity	BOTH
Low rock stresses or poor confinement of the rock above tunnel axis require more than anticipated pre-bolting (spiling) reducing productivity and increasing cost.	NATM
Crushed or blocky rock from the face, or walls and roof close to the face before proper rock support has been installed reduces productivity and increases cost.	BOTH
Movement of heavy plant , equipment and people	BOTH
Loss of power, including lighting and ventilation	BOTH
Restricted visibility and communications during tunnel excavation	BOTH
Logistics and volume of muck disposal	TBM
Lack experience in certain specialized tunnel methods.	BOTH
Ability to safely evacuate people from the underground workspace in an emergency.	BOTH
Inexperience of workforce negatively influences tunneling advance rates	BOTH
Breakdown of equipment leaves face unsupported for longer than natural stand up time.	BOTH
Dust suppression and tunnel ventilation requirements much higher than anticipated to control the high levels of quartzite dust to safe level during mining. Settled dust reduces equipment performance.	BOTH
Delays in obtaining materials for equipment repair	BOTH
Insufficient laydown for precast segments	TBM
Inability to support mucking rate	TBM
Non -continuous mining through fault zones results in blockages and or potential machine stoppages	

applied based upon optimistic, most likely and pessimistic advance rates for both the NATM and TBM methods. These ranges of advance rate are presented in the Tables 5 and 6 (Samsung C&T, 2010b). Advance rates for the NATM approach were assessed based upon 9 groups of support categories, as shown in Table 5. Similarly, TBM advance rates were assessed in the five predominant ground types I through V, as shown in Table 6. Normal practice is to assess the most likely advance rates in various ground conditions requiring varying levels of excavation sequencing and ground support.

The base tunnel construction cost was assumed as ₩200B for both tunneling methods. The NATM and TBM tunneling costs breakdown can not be given in this paper. Although the base tunneling cost is not as exact as building up a proper cost estimate for the project, the prototypical cost estimate for similar size

tunnels was used and it is considered as a reasonable comparison for purposes of the risk assessment. Accuracy was considered less important than determining if there were orders of magnitude differences in cost when risk and uncertainty was applied to each of the construction alternatives.

The risk analysis was completed using Monte Carlo simulation in Primavera Risk Analysis. Monte Carlo simulation is a simulation technique for forecasting the range of results most likely to occur. In this technique, each input variable is sampled at random from its probability distribution, and the input variables are integrated to calculate the response variable. This process is repeated to obtain a large set of values of the response variable. From this set, one can calculate the range of the response variable associated with specified confidence levels.

**Table 5.** Optimistic, Most Likely and Pessimistic Advance Rates for NATM Excavation and Support

Support Type	Length (m)	% Length of Tunnel	Optimistic AR (m/wd)	Most likely AR (m/wd)	Pessimistic AR (m/wd)
P-6-2	100	2	0.75	0.5	0.25
P-6/P-6-1/SP6	189	5	1	0.75	0.5
SP5	37	1	2	1.5	1
P-3/P-4/P-5	1168	30	3	2	1
SP-3/SP-4	1679	44	4	2	1
P-2	220	6	5	3	1.5
SP-2	260	7	4	3	1.5
F-2	105	3	2	1.5	1
F-1	82	2	1	0.75	0.5

**Table 6.** Optimistic, Most Likely and Pessimistic Advance Rates for TBM Excavation and Support

Ground Type	Tunnel Length		RMR (max)	Q	Optimistic AR (m/wd)	Most likely AR (m/wd)	Pessimistic AR (m/wd)
	(m)	(%)					
Type I	0	0	>85	10~100	18	9	3
Type II	2140	27	85	1~10	20	18	15
Type III	2070	32	56	0.1~1	20	13	6
Type IV	2540	32	30	0.01~0.1	14	7	3
Type V	970	15	22	0.001~0.01	6	3	1

## 4.2 Analysis Results

It would appear that, assuming there are adequate skilled labor resources available to drive multiple headings consecutively, advance rates with the NATM approach in these ground conditions, although slower than the TBM approach, are more predictable (Parsons Brinckerhoff, 2010). Risks, however, are prevalent when tunneling in such varied rock masses. Risks likely to slow advance rates include flooding, collapse of the face, rock spalling, slabbing and or rock wedge falls. Unconsolidated material within or in close proximity to the fault zones, or standing under water pressure

may cause immediate collapse at the face if exposed before adequate treatment.

The analysis results using Monte Carlo simulation are shown in Fig. 1 and 2. These costs reflect tunneling costs in current year. Extended overhead costs were considered to be ₩97 mil for each working day beyond the deterministic completion date until project completion (Parsons Brinckerhoff, 2010). The analysis results are summarized in Tables 7 and 8.

A robust construction schedule incorporates the best estimate of the duration activity, correct logic between successive and interconnecting activities, uncertainty




Fig. 1. Monte Carlo Simulation with Discrete Risk Events and Risks Contributing to Uncertainty






Fig. 2. Monte Carlo Simulation with Risks Contributing to Uncertainty Only

Table 7. Likelihood of Meeting Deterministic Cost (Base Cost ₩200B) and Schedule (Base Schedule 1,400 days for NATM, 1,800 days for TBM)

Method	Model for Uncertainty Only		Model for Uncertainty and Risk Events	
	Cost	Schedule	Cost	Schedule
NATM	49%	72%	6%	51%
TBM	<1%	7%	<1%	5%

Table 8. Estimated Tunnel Construction Costs and Schedule for 50% Confidence Levels

Method	Model for Uncertainty Only		Model for Uncertainty and Risk Events	
	Cost	Schedule	Cost	Schedule
NATM	₩200B	54 mo	₩239B	57 mo
TBM	₩246B	78 mo	₩256B	79 mo

---

and risk. If only the uncertainty in productivity (i.e. advance rates) is considered for the analysis, it would appear that there is a reasonably high confidence (> 70%) that the planned 57 months from mobilization to completion of tunnel excavation and lining for the NATM approach can be achieved. However if discrete risk events are taken into consideration the confidence level reduces to 50%.

The TBM approach appears more unpredictable and therefore presents a higher risk. If uncertainty in advance rates is applied to each of the five ground types there is very low confidence (< 1%) that the planned 65 months between mobilization and completion of tunnel excavation can be achieved and that the project can be completed at or under the estimated cost. There is a 50% probability that tunneling (assuming one TBM) could take 78 months or longer.

An analysis was performed to assess the sensitivity of the tunnel advance rates to the output of the risk analysis. The optimistic daily advance rates for the TBM were doubled in the model. The outcome was that this reduced the 50% probability of achieving completion of tunneling (assuming one TBM) from 78 months to 74 months. This would indicate, as expected, that in these ground conditions the success of the TBM option is more dependent upon the occurrence (or non-occurrence) of risk events than it is by general uncertainty in advance rates.

## 5. Discussion and Conclusion

A comparative risk analysis of TBM against NATM tunneling was carried out in this paper. The main purpose of this study is to assess whether the project using NATM or TBM method can achieve the planned excavation duration and bring the project within the estimated bid price. The analysis results would help to decide which tunneling method alternative needs to be selected to complete the mixed-face large urban tunnel project with the least time and cost. For NATM,

the risk analysis found that the project had a 72% confidence in completing the project within the estimated time and a 49% confidence in completing the project at or under the estimated cost. For the TBM method, the risk analysis found that the project had a <1% confidence in completing the project within the estimated time and a <1% confidence in completing the project at or under the estimated cost. It should be noted that the risk analysis is only applied to this tunnel project with specific geological conditions and other contract requirements.

Risk in tunneling is unavoidable, and a risk management and mitigation plan should be implemented to manage risks to an acceptable level. Thorough and transparent risk management systems have proven effective and beneficial on major projects all over the world. There are several actions required to ensure that the risk management framework can be carried forward through the project design and construction stages. The following are some recommendations of tasks and strategic planning arrangements and on how the risk management process moves forward (URS, 2005).

- Create a risk management manual for the project that will provide a detailed framework of how each aspect of the risk management program fits with the ongoing project tasks
- Designate a Project Risk Coordinator that has overall responsibility for maintenance of the risk management program and coordinates the various risk registers in use.
- Carry out independent audits on the overall project risk register, including all the cascading work activity risk registers
- Generate and maintain risk registers at the work activity level. The owner must make sure that relevant risk registers are transferred as part of the design builder's Contract so that they become part of the project requirements

## References

1. Barla G and Pelizza S. (2000) TBM tunnelling in difficult ground conditions.
2. Barton N. (2000) *TBM Tunneling in Jointed and Faulted Rock*, Taylor & Francis, p. 184.
3. Holen H. and Anlegg S. (1998) TBM vs drill & blast tunnelling, *Norwegian TBM Society*, pp. 95~98.
4. Huang R. (2008) *The Shanghai Yangtse River Tunnel: Theory, Design, and Construction*, p.360.
5. Parsons Brinckerhoff, Inc. (2010) *Tunnel Options Risk Assessment for OOO Road Expansion Project*.
6. Samsung C&T (2010a) *OOO Road Expansion Project – Geotechnical Investigation Report*.
7. Samsung C&T (2010b) *OOO Road Expansion Project – Tunnel Design Report*.
8. Tarkoy P.J. (1996) Comparing TBMs with drill and blast excavation, *Int'l J. of Rock Mech. and Mining Sci. and Geomech. Abst.*, Vol. 33, No. 4, pp. 186A~186A(1).
9. URS Corporation (2005) *OOO Tunnel Project – Qualitative Risk Assessment Report*.
10. Kim Y., Hencher S.R, Yoon Y., and Cho S. (2002) Determination of the construction method for Young Dong Tunnel by risk assessment, *Tunneling Technology, KTA*, Vol. 4, No. 1, pp. 13~25.

---

접수일(2010.8.31), 수정일(2010.9.23), 게재확정일(2011.1.10)